

PROJECT ADDRESS	REV0- BE-PR-								
Date of submission	Please see next tab for consolidated list								
Date of plans	Please confirm sales tax over material								
Comments									
LUMBER	\$	12,750							

SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
	Exterior Wall Framing @ Lower Level:								
1	2x6x16' #2 HF pt	9	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
2	2x6x116-5/8" #2 HF	217	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
3	2x6x16' #2 HF	27	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
4	1/2" APA Rated Plywood (4x8)	43	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Sheathing @ Exterior Wall
5	10'x125' Tyvek	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Building Wrap
6	2"x165' Tyvek Tape	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wrap Tape
	Interior Wall Framing @ Lower Level:								
7	2x4x16' #2 DF pt	19	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
8	2x6x16' #2 DF pt	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
9	2x4x116-5/8" #2 HF	265	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
10	2x4x12' #2 HF	28	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
11	2x6x116-5/8" #2 HF	103	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
12	2x4x16' #2 HF	57	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
13	2x6x16' #2 HF	18	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
	Exterior Header/ Beam @ Lower Level:								
14	8x16x16' #1 DF	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
15	8x16x14' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
16	8x16x12' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
17	8x16x6' #1 DF	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
18	8x16x20' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
19	1-3/4"X9-1/2" LVL (2/10')	20	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
20	1-3/4"X9-1/2" LVL (3/8')	24	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
21	1-3/4"X11-7/8" LVL (3/8')	24	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
	Studs Packs @ Main Level:								
22	2x6x116-5/8" #2 HF	47	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Studs Packs
23	1-3/4"x5-1/2" LVL (6/10')	60	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Studs Packs
24	10x10x10' #1 DF	10	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Timber Column

PROJECT ADDRESS	REVO- BE-PR-								
Date of submission	Please see next tab for consolidated list								
Date of plans	Please confirm sales tax over material								
Comments									
LUMBER	\$	12,750							

SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
25	8x8x6' #1 DF	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Timber King Post
26	6x6x10' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Timber Column
	Studs Packs @ Lower Level:								
27	2x6x116-5/8" #2 HF	86	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Studs Packs
28	1-3/4"x5-1/2" LVL (6/10')	60	LF	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Column
29	6x6x10' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Timber Column
30	10x10x10' #1 DF	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Timber Column
	Interior Header/ Beam @ Lower Level:								
31	1-3/4"x14" LVL (6/18')	108	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
32	1-3/4"x14" LVL (2/10')	20	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
33	1-3/4"x14" LVL (3/24')	72	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
34	1-3/4"x16" LVL (7/20')	140	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
35	1-3/4"x14" LVL (2/29')	58	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
36	1-3/4"x14" LVL (3/17')	51	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
37	1-3/4"x14" LVL (1/3')	3	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
38	1-3/4"x14" LVL (1/4')	4	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
39	1-3/4"x14" LVL (1/12')	12	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
40	1-3/4"x11-7/8" LVL (1/7')	7	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ lower Level
	Sub-Floor Framing @ Main Level:								
41	14" BCI 60-2.0 FJ (8'-Long)	15.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
42	14" BCI 60-2.0 FJ (12'-Long)	18.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
43	14" BCI 60-2.0 FJ (16'-Long)	5.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
44	14" BCI 60-2.0 FJ (18'-Long)	20.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
45	14" BCI 60-2.0 FJ (20'-Long)	56.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
46	14" BCI 60-2.0 FJ (10'-Long)	25.0	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Joist @ 16" O.C
47	1-3/4"x9-1/2" LVL (7/10')	70	EA	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Floor Joist @ 16" O.C
48	1-3/4"x9-1/2" LVL (55/12')	660	EA	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Floor Joist @ 16" O.C
49	1-3/4"x9-1/2" LVL (9/8')	72	EA	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Floor Joist @ 16" O.C
50	1-3/4"x9-1/2" LVL (3/6')	18	EA	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Floor Joist @ 16" O.C

PROJECT ADDRESS	REV0- BE-PR-								
Date of submission	Please see next tab for consolidated list Please confirm sales tax over material								
Date of plans									
Comments									
LUMBER	\$	12,750							

SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
51	3/4" APA Rated T & G Plywood (4x8)	115	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Floor Sheathing
52	29oz Adhesive	29	EA	\$ -	\$ -	\$ -	\$ -	\$ -	
	Exterior Wall Framing @ Main Level :								
53	2x6x16' #2 HF pt	19	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
54	2x6x116-5/8" #2 HF	502	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
55	2x6x16' #2 HF	57	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
56	1/2" APA Rated Plywood (4x8)	93	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Sheathing @ Exterior Wall
57	10'x125' Tyvek	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Building Wrap
58	2"x165' Tyvek Tape	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wrap Tape
	Interior Wall Framing @ Main Level:								
59	2x4x16' #2 HF	10	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
60	2x6x16' #2 HF	12	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Bottom Plate
61	2x4x116-5/8" #2 HF	246	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
62	2x4x24' #2 HF	38	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C Chimney
63	2x6x116-5/8" #2 HF	264	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Wall Studs @ 16" O.C
64	2x4x16' #2 HF	30	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
65	2x6x16' #2 HF	36	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Double Top Plate & Mid span Blocking
	Exterior Header/ Beam @ Main Level:								
66	1-3/4"x16" LVL (1/18')	18	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
67	8x14x18' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
68	8x14x16' #1 DF	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
69	10x14x16' #1 DF	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
	Interior Header/ Beam @ main Level:								
70	1-3/4"x9-1/2" LVL (6/18')	108	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
71	1-3/4"x9-1/2" LVL (6/16')	96	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
72	1-3/4"x11-7/8" LVL (3/9')	27	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level

PROJECT ADDRESS	REVO- BE-PR-								
Date of submission	Please see next tab for consolidated list								
Date of plans	Please confirm sales tax over material								
Comments									
LUMBER	\$	12,750							

SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
73	3-1/4"x7-1/4" LVL (1/6')	6	LF	\$ -	\$ -	\$ -	\$ -	\$ -	Header @ Main Level
	Roof Framing:								
74	Engineering Wood Roof Girder (18' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Girder Truss
75	Engineering Wood Roof Girder (14' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Girder Truss
76	4x12x8' #1 DF	10	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
77	4x12x10' #1 DF	19	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
78	4x12x16' #1 DF	5	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
79	4x12x14' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
80	4x12x12' #1 DF	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
81	4x12x18' #1 DF	18	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Rafters @ 32" O.C
82	Type-F Roof Truss (6' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
83	Type-F Roof Truss (8' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
84	Type-F Roof Truss (10' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
85	Type-F Roof Truss (12' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
86	Type-F Roof Truss (13' Long)	9	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
87	Type-F Roof Truss (4' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
88	Type-F Roof Truss (14' Long)	7	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
89	Type-F Roof Truss (15' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
90	Type-C Roof Truss (14' Long)	20	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
91	Type-B Roof Truss (16' Long)	20	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
92	Type-A Roof Truss (16' Long)	9	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
93	Type-A Roof Truss (12' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
94	Type-K Roof Truss (9' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
95	Type-K Roof Truss (13' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
96	Type-K Roof Truss (5' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
97	Type-K Roof Truss (1' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
98	Type-P Roof Truss (12' Long)	7	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
99	Type-P Roof Truss (10' Long)	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
100	Type-P Roof Truss (8' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
101	Type-P Roof Truss (6' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
102	Type-P Roof Truss (4' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
103	Type-P Roof Truss (2' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
104	Type-E Roof Truss (13' Long)	9	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C

PROJECT ADDRESS	REVO- BE-PR-								
Date of submission	Please see next tab for consolidated list								
Date of plans	Please confirm sales tax over material								
Comments									
LUMBER	\$	12,750							

SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
105	Type-M Roof Truss (4' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
106	Type-M Roof Truss (2' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
107	Type-M Roof Truss (6' Long)	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
108	Type-M Roof Truss (8' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
109	Type-N Roof Truss (10' Long)	12	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
110	Type-N Roof Truss (8' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
111	Type-N Roof Truss (6' Long)	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
112	Type-H Roof Truss (14' Long)	7	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Trusses @ 24" O.C
113	2x8x8' #1 DF	8	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Ladder Framed @ 24" O.C
114	2x8x6' #1 DF	16	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Ladder Framed @ 24" O.C
115	2x8x4' #1 DF	9	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Ladder Framed @ 24" O.C
	Roof Decking:								
116	5/8" APA Rated Plywood (4x8)	195	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Sheathing
117	19/32" Ply Clips	780	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Decking Accessories
118	30# Felt, 3'x144' Roll	15	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Decking Accessories
119	Ice and Water Shield, 3'x66.7' Roll	32	SQ	\$ -	\$ -	\$ -	\$ -	\$ -	Roof Decking Accessories
	BLOCKING:								
120	2X10X16' #2 HF PT	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -	PT Plate
121	2X6X16' #2 HF PT	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Blocking
122	2X8X16' #2 HF	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Blocking
123	2X12X16' #2 HF	14	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Blocking
124	1-3/4"x11-1/4" LVL (10/12')	121	LF	\$ -	\$ -	\$ -	\$ -	\$ -	LVL Rim
	SIMPSON HARDWARES:								
125	Simpson W14	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
126	Simpson HHB816	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
127	Simpson HWU3.56/14	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
128	Simpson HWU3.50/14	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
129	Simpson HWU7.12/16	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
130	Simpson U610R Hanger	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares

PROJECT ADDRESS	REV0- BE-PR-								
Date of submission	Please see next tab for consolidated list								
Date of plans	Please confirm sales tax over material								
Comments									
LUMBER	\$	12,750							
SR #	DESCRIPTION	QTY.	UNIT	LABOR UNIT COST	MATERIAL UNIT COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL COST	REMARKS
131	Simpson HHUS410 Hanger	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -	Simpson Hardwares
132	Simpson Strong Tie Allowance:	1	LS		\$ 12,000		\$ 12,000	\$ 12,000	
	Note: 10% Wastage is figured with all quantities								
						Total Labor	Total Material		
						\$ -	\$ 12,000		
Sub Total								\$ 12,000	
Sales Tax over Material							6.25%	\$ 750	
Total Lumber								\$ 12,750	

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
	Consolidated List		
1	1/2" APA Rated Plywood (4x8)	136	EA
2	10x10x10' #1 DF	14	EA
3	10'x125' Tyvek	5	EA
4	10x14x16' #1 DF	3	EA
5	1-3/4"x11-1/2" LVL	121	LF
6	1-3/4"x11-7/8" LVL (1/7')	7	LF
7	1-3/4"x11-7/8" LVL (3/8')	24	LF
8	1-3/4"x11-7/8" LVL (3/9')	27	LF
9	1-3/4"x14" LVL (1/12')	12	LF
10	1-3/4"x14" LVL (1/3')	3	LF
11	1-3/4"x14" LVL (1/4')	4	LF
12	1-3/4"x14" LVL (2/10')	20	LF
13	1-3/4"x14" LVL (2/29')	58	LF
14	1-3/4"x14" LVL (3/17')	51	LF
15	1-3/4"x14" LVL (3/24')	72	LF
16	1-3/4"x14" LVL (6/18')	108	LF
17	1-3/4"x16" LVL (1/18')	18	LF
18	1-3/4"x16" LVL (7/20')	140	LF
19	1-3/4"x5-1/2" LVL (6/10')	120	LF

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
20	1-3/4"X9-1/2" LVL (2/10')	20	LF
21	1-3/4"x9-1/2" LVL (3/6')	18	LF
22	1-3/4"X9-1/2" LVL (3/8')	24	LF
23	1-3/4"x9-1/2" LVL (55/12')	660	LF
24	1-3/4"x9-1/2" LVL (6/16')	96	LF
25	1-3/4"x9-1/2" LVL (6/18')	108	LF
26	1-3/4"x9-1/2" LVL (7/10')	70	LF
27	1-3/4"x9-1/2" LVL (9/8')	72	LF
28	14" BCI 60-2.0 FJ (10'-Long)	25	EA
29	14" BCI 60-2.0 FJ (12'-Long)	18.0	EA
30	14" BCI 60-2.0 FJ (8'-Long)	15.0	EA
31	14" BCI 60-2.0 FJ (16'-Long)	5.0	EA
32	14" BCI 60-2.0 FJ (18'-Long)	20.0	EA
33	14" BCI 60-2.0 FJ (20'-Long)	56.0	EA
34	19/32" Ply Clips	780	EA
35	2"x165' Tyvek Tape	10	EA
36	29oz Adhesive	29	EA
37	2X10X16' #2 HF PT	1	EA
38	2X12X16' #2 HF	14	EA
39	2x4x116-5/8" #2 HF	511	EA
40	2x4x12' #2 HF	28	EA

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
41	2x4x16' #2 DF pt	19	EA
42	2x4x16' #2 HF	97	EA
43	2x4x24' #2 HF	38	EA
44	2x6x116-5/8" #2 HF	1,219	EA
45	2x6x16' #2 DF pt	6	EA
46	2x6x16' #2 HF	150	EA
47	2x6x16' #2 HF pt	31	EA
48	2X8X16' #2 HF	6	EA
49	2x8x4' #1 DF	9	EA
50	2x8x6' #1 DF	16	EA
51	2x8x8' #1 DF	8	EA
52	3/4" APA Rated T & G Plywood (4x8)	115	EA
53	30# Felt, 3'x144' Roll	15	EA
54	3-1/4"x7-1/4" LVL (1/6')	6	LF
55	4x12x10' #1 DF	19	EA
56	4x12x12' #1 DF	1	EA
57	4x12x14' #1 DF	1	EA
58	4x12x16' #1 DF	5	EA
59	4x12x18' #1 DF	18	EA
60	4x12x8' #1 DF	10	EA
61	5/8" APA Rated Plywood (4x8)	195	EA

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
62	6x6x10' #1 DF	2	EA
63	8x14x16' #1 DF	3	EA
64	8x14x18' #1 DF	1	EA
65	8x16x12' #1 DF	1	EA
66	8x16x14' #1 DF	1	EA
67	8x16x16' #1 DF	4	EA
68	8x16x20' #1 DF	1	EA
69	8x16x6' #1 DF	2	EA
70	8x8x6' #1 DF	2	EA
71	Engineering Wood Roof Girder (18' Long)	2	EA
72	Engineering Wood Roof Girder (14' Long)	2	EA
73	Type-F Roof Truss (6' Long)	1	EA
74	Type-F Roof Truss (8' Long)	1	EA
75	Type-F Roof Truss (10' Long)	1	EA
76	Type-F Roof Truss (12' Long)	1	EA
77	Type-F Roof Truss (13' Long)	9	EA
78	Type-F Roof Truss (4' Long)	1	EA
79	Type-F Roof Truss (14' Long)	7	EA
80	Type-F Roof Truss (15' Long)	2	EA
81	Type-C Roof Truss (14' Long)	20	EA
82	Type-B Roof Truss (16' Long)	20	EA

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
83	Type-A Roof Truss (16' Long)	9	EA
84	Type-A Roof Truss (12' Long)	2	EA
85	Type-K Roof Truss (9' Long)	1	EA
86	Type-K Roof Truss (13' Long)	1	EA
87	Type-K Roof Truss (5' Long)	1	EA
88	Type-K Roof Truss (1' Long)	1	EA
89	Type-P Roof Truss (12' Long)	7	EA
90	Type-P Roof Truss (10' Long)	4	EA
91	Type-P Roof Truss (8' Long)	2	EA
92	Type-P Roof Truss (6' Long)	1	EA
93	Type-P Roof Truss (4' Long)	1	EA
94	Type-P Roof Truss (2' Long)	1	EA
95	Type-E Roof Truss (13' Long)	9	EA
96	Type-M Roof Truss (4' Long)	2	EA
97	Type-M Roof Truss (2' Long)	2	EA
98	Type-M Roof Truss (6' Long)	2	EA
99	Type-M Roof Truss (8' Long)	1	EA
100	Type-N Roof Truss (10' Long)	12	EA
101	Type-N Roof Truss (8' Long)	1	EA
102	Type-N Roof Truss (6' Long)	1	EA
103	Type-H Roof Truss (14' Long)	7	EA

PROJECT	0.00		
ADDRESS	0.00		
SR #	DESCRIPTION	QTY	UNIT
104	Ice and Water Shield, 3'x66.7' Roll	32	EA
105	Simpson W14	6	EA
106	Simpson HHB816	2	EA
107	Simpson HWU3.56/14	4	EA
108	Simpson HWU3.50/14	2	EA
109	Simpson HWU7.12/16	2	EA
110	Simpson U610R Hanger	4	EA
111	Simpson HHUS410 Hanger	6	EA
112	Simpson Strong Tie Allowance: (\$12000)	1	LS
	Note: 10% Wastage is figured with all quantities.		